

CITY COLLEGE OF SAN FRANCISCO
DEPARTMENT OF FACILITIES
Creative Arts Steam-line Replacement

ADDENDUM 1

PROJECT# Creative Arts Steam-line Replacement

DATE# September 1, 2011

OWNER# San Francisco Community, College District CCSF . ID NO# 111-111
% ' Fri 0a 1a 2l *) a, DSA FILE NO# N3A
San Francisco CA 4/55! DSA APP# NO# N3A

Notice is hereby given to all

EXHIBIT A

Scope of Work

Furnish and install new underground high-pressure steam and condensate return pipe to replace the existing high pressure steam line between Cloud Hall and Creative Arts building at Ocean Campus

Furnish and install approximately 1000 feet of 12" high pressure steam steel pipe per specifications. Furnish and install approximately 1000 feet of 4" & condensate return steel pipe per specifications. Contractor to field verify existing pipe thickness, final pipe lengths and coordinate optimal pipe routing to avoid existing utilities and infrastructure. Contractor to maintain all ADA path of travel and existing utility lines. Provide required temporary structures such as trench plates, temporary stairs, barricades, and temporary ramps to maintain vehicular and pedestrian traffic. Scope includes necessary insulation, banding, all pipe supports, corrosion resistance, fittings and weld fittings, anchors, indicator, warning tape, end seals and gland seals for a full functional steam system from Cloud Hall to Creative Arts. Include hardscape, landscape, and asphalt restoration per suggested pipe routes. Contractor to assume shoring is required for any trenches through existing asphalt or concrete. Contractor to assume . /